

DATE : 08/29/2024
ATTENTION : Mr. Jeycee Manalili
PROJECT : OFFICE ROOM RENOVATION
LOCATION : PACKAGING AREA
SUBJECT : MATERIAL AND LABOR COST FOR
NEW BUILDING FACILITIES & RETROFITING

CUSTOMER ID NO. : 10
QUOTATION NO. : QUO2025_92
VALIDITY : 16 days
REPRESENTATIVE : Renante Vega
CONTACT PERSON : 0950-8228-147



Dear Ms. Juselle Magpantay

I hereby submit our proposal in relation to the above-mentioned subject which is amounting to FIVE MILLION FIVE HUNDRED SEVENTY TWO THOUSAND SEVENTY SEVEN AND 84/100 PESOS.
Please see attached breakdown

	DESCRIPTION			LABOR COST		MATERIAL COST		
				UNIT PRICE	SUB-TOTAL	UNIT PRICE	SUB-TOTAL	
A	GENERAL REQUIREMENTS							
1.0	Mobilization and Demobilization (30days)	1.00	lot			80,000.00	80,000.00	80,000.00
2.0	Safety Engineering (Enclosure,Signage PPE and Fulltime Safety Officer)	1.00	lot			60,000.00	60,000.00	60,000.00
3.0	Scaffolding and Support	1,206.00	sqm			100.00	120,600.00	120,600.00
4.0	Cleaning and Hauling of debris	1,206.00	sqm			60.00	72,360.00	72,360.00
5.0	Documentation & Reports	1.00	lot			30,000.00	30,000.00	30,000.00
SUB - TOTAL I								362,960.00
B	CIVIL WORKS							
1.0	Hanger & Support for ceiling reinforcement to lower ceiling from 12 meter to 3 meters	800.00	sqm	250.00	200,000.00			200,000.00
	Tubular 2x3 inch x 1.5mm thk x 20ft	36.00	pcs	50.00	1,800.00	715.00	25,740.00	27,540.00
	Tubular 2x2 inch x 1.5mm thk x 20ft	68.00	pcs	40.00	2,720.00	624.00	42,432.00	45,152.00
	Angle bar 2x2 inch x 4mm thk x 20ft	50.00	pcs	35.00	1,750.00	746.20	37,310.00	39,060.00
	Roundbar 3/8	140.00	pcs	20.00	2,800.00	334.10	46,774.00	49,574.00
	Threaded turn buckle 10mm	90.00	pcs	15.00	1,350.00	150.00	13,500.00	14,850.00
	Dyna bolt 3/8	60.00	pcs	10.00	600.00	48.00	2,880.00	3,480.00
	Consumables	1.00	lot			10,000.00	10,000.00	10,000.00
2.0	CEILING WORKS							
	Installation of tile ceiling 2ft x 4ft acoustic ceiling board (approximately 800sq mtrs)	800.00	sqm	250.00	200,000.00			200,000.00
	Acoustic ceiling board 2ft x 4ft	1,120.00	pcs			462.00	517,440.00	517,440.00
	Suspension System (main tee,cross,etc.)10ft	210.00	pcs			168.00	35,280.00	35,280.00
	Cross tee(4ft)	1,050.00	pcs			70.00	73,500.00	73,500.00
	Wall Angle and Fasteners	50.00	pcs			168.00	8,400.00	8,400.00
	Consumables	1.00	lot			6,000.00	6,000.00	6,000.00
3.0	LOBBY AREA AND MAIN ENTRANCE							
	Labor for partition walls	103.00	sqm	299.00	30,797.00			30,797.00
	gypsum board 4ft x 8ft x 9mm thck double wall	103.00	sqm			315.00	32,445.00	32,445.00
	Metal Studs & track (Framing System)	51.80	sqm			546.00	28,282.80	28,282.80
	Joint Compound, Screws, Tape, Accessories	1.00	lot	5,000.00	5,000.00	6,000.00	6,000.00	11,000.00
4.0	OFFICE AND ACCESSORIES							
	Labor for partition walls	168.00	sqm	299.00	50,232.00			50,232.00
	gypsum board 4ft x 8ft x 9mm thck double wall	168.00	sqm			315.00	52,920.00	52,920.00
	Metal Studs & track (Framing System)	84.00	sqm			546.00	45,864.00	45,864.00
	Joint Compound, Screws, Tape, Accessories	1.00	lot			9,000.00	9,000.00	9,000.00
	Fixed Window, 1.2m x 1.0m Aluminum tubular frame w/ Ordinary Glass 6mm thk Finished: coated white (Lobby and accessories)	2.00	sets	2,500.00	5,000.00	7,800.00	15,600.00	20,600.00
	Sliding door 800mm x 2100mm, Aluminum white glow finish,tinted (Lobby and accessories)	2.00	sets	6,500.00	13,000.00	14,400.00	28,800.00	41,800.00
	Fixed window, tinted, 2 frame x 1.5M X 1.5M (for office)	1.00	set	6,500.00	6,500.00	12,000.00	12,000.00	18,500.00
	Wood Panel Door and jamb 900mm x 2100mm w/ accessories (Accessories and Office)	2.00	set	2,500.00	5,000.00	11,050.00	22,100.00	27,100.00
	Epoxy painting, portions only	1.00	lot			5,000.00	5,000.00	5,000.00
	Painting of double wall partitions 2 coats each side (lobby,main entrance,Accessories and Office)	319.00	sqm	120.00	38,280.00	234.00	74,646.00	112,926.00
SUB - TOTAL II								1,716,742.80
C	ELECTRICAL WORKS							
1.0	Feeder line from transformer Room to Electrical Room approximately 45mtrs 80mm2,Red,Yellow,Black with 22mm2 green"	45.00	mtrs	200.00	9,000.00			9,000.00
	80mm2 THHN Copper Wire (Red, Yellow, Black - 3 runsx 45m)	135.00	mtrs			959.40	129,519.00	129,519.00
	22mm2 THHN Copper Wire (Green - ground, 45m)	45.00	mtrs			325.00	14,625.00	14,625.00
	HDPE Conduit or PVC pipe (4") + accessories (45m)	45.00	mtrs			259.50	11,677.50	11,677.50
	Electrical Tapes,Connectors, Consumables	1.00	lot			6,500.00	6,500.00	6,500.00
2.0	Labor (assembly, testing, installation)							
	Main Distribution Panel (MDP)							
	Main 300AT / 400AF, 3Phase	1.00	lot	12,000.00	12,000.00	98,160.00	98,160.00	110,160.00
	Branches 3 x 150AT/200AF, 3P/ 1x200AT/200AF, 3P							
	MDP Enclosure (powder-coated, IP44/IP55)	1.00	set					
	Main MCCB 300AT / 400AF, 3P	1.00	pc					
	Branch MCCB 150AT / 200AF, 3P	3.00	pcs					
	Branch MCCB 200AT / 200AF, 3P	1.00	pc					
	Copper Bus Bar, Lugs, Terminal Blocks	1.00	pc					

	Wiring, Labels, Tags	1.00	lot					
3.0	Labor (assembly, wiring, testing, installation) Distribution Panel - PP-1 (ACU & Lighting) Enclosure: NEMA1 Main Breaker: 150AT/200AF, 3P Branches: 6X40AT/100AF, 2P / 4X30AT/100AF, 2P / 6X20AT/100AF, 2P	1.00	lot	10,000.00	10,000.00	58,400.00	58,400.00	68,400.00
	Panel Enclosure (NEMA 1, powder-coated)	1.00	set					
	Main MCCB 150AT/200AF, 3P	1.00	pc					
	MCCB 40AT/100AF, 2P (Branches)	6.00	pcs					
	MCCB 30AT/100AF, 2P (Branches)	4.00	pcs					
	MCCB 20AT/100AF, 2P (Branches)	6.00	pcs					
	Internal wiring, bus bars, lugs, labels	1.00	lot					
4.0	Labor (assembly, wiring, testing, installation) Distribution Panel - PP-2 (Production Sewing Machines) Enclosure: NEMA1 Main Breaker: 150AT/200AF, 3P Branches: 6X40AT/100AF, 2P	1.00	lot	9,000.00	9,000.00	58,400.00	58,400.00	67,400.00
	Panel Enclosure (NEMA 1, powder-coated)	1.00	set					
	Main MCCB 150AT/200AF, 3P	1.00	pc					
	Branch MCCB 40AT/100AF, 2P	6.00	pcs					
	Internal Busbar, Terminals, Labels	1.00	lot					
	Wiring, Lugs, Accessories	1.00	lot					
5.0	Labor (cable pulling, conduit install, termination) Feeder line for PP-1 & PP-2 Distance: 26 mtrs + 27mtrs = 53mtrs total Wire size: 30mm2 THHN, red,yellow,black (3-phase)	53.00	mtrs	150.00	7,950.00		-	7,950.00
	30mm ² THHN Wire (Red, Yellow, Black — 3 runs x 53m)	159.00	mtrs			406.90	64,697.10	64,697.10
	Conduit (PVC/HDPE) & accessories	53.00	mtrs			519.60	27,538.80	27,538.80
	Pull boxes, couplings, tape, lugs, clamps	1.00	lot			4,500.00	4,500.00	4,500.00
6.0	Labor (pulling, termination, testing) Ground wire for PP-1 & PP-2 Legth: 26m + 27m = 53meters Specs: 14mm2 green THHN (Copper)	53.00	mtrs	80.00	4,240.00		-	4,240.00
	14mm ² THHN Copper Wire (Green)	53.00	mtrs			234.00	12,402.00	12,402.00
	Pull boxes, clips, connectors, consumables	1.00	lot			4,000.00	4,000.00	4,000.00
7.0	Labor(cutting, Threading,Installation)	60.00	mtrs	120.00	7,200.00		-	7,200.00
	IMC Pipe Conduit, 1-1/4 , 3.0m legth (standard)	35.00	pcs			1,340.00	46,900.00	46,900.00
	IMC Coupling,Locknuts, Bushings	20.00	pcs			1,050.00	21,000.00	21,000.00
8.0	Labor(cutting, Threading,Installation)	10.00	pcs	80.00	800.00		-	800.00
	IMC elbow, 1-1/4	10.00	pcs			429.00	4,290.00	4,290.00
9.0	Labor (support framing + power install) Ocerhead Power Strip for 24 Sewing Machine (30meters)	30.00	mtrs	350.00	10,500.00		-	10,500.00
	G.I. Pipe 1/2" Sch. 20 (15 pcs @ 6m)	90.00	pcs			220.00	19,800.00	19,800.00
	C-Purlins 2"x4" x 1.5mm thk (30 meters)	180.00	mtrs			250.00	45,000.00	45,000.00
	Brackets, clamps, screws, bolts	1.00	lot			2,500.00	2,500.00	2,500.00
	Electrical Boxes, Receptacles, Wiring	24.00	sets			350.00	8,400.00	8,400.00
10.0	Labor (installation, wiring, termination) Power Outlet System for 144 Sewing Machines Specification: Twistlock Type, 20A, 3-Prong, Panasonic (Single Phase)	144.00	mtrs	120.00	17,280.00		-	17,280.00
	Panasonic 3-Prong Twistlock Outlet, 20A	144.00	lot			450.00	64,800.00	64,800.00
	Utility Box, Faceplate, Screws	144.00	mtrs			100.00	14,400.00	14,400.00
	THHN Wires (12 AWG), Approx. 3m per outlet	432.00	mtrs			25.00	10,800.00	10,800.00
	Circuit Breakers (assume 12 circuits, 12 CBs)	12.00	pcs			850.00	10,200.00	10,200.00
	PVC Conduits, Clamps, Fittings (estimated 150m)	150.00	mtrs			30.00	4,500.00	4,500.00
11.0	Labor (termination, plug wiring)(power outlet) Power Plug — 144 Sets (Panasonic Twistlock, 20A, 3-Prong)	153.00	pcs	80.00	12,240.00	640.00	97,920.00	110,160.00
	Panasonic Twistlock Plug, 20A, 3-Prong(power plug)	153.00	pcs	80.00	12,240.00	550.00	84,150.00	96,390.00
	Wire connectors, clamps, consumables	1.00	lot			3,500.00	3,500.00	3,500.00
12.0	Labor (wiring, pulling, termination) Electrical line for sewing machine, 3.5mm2 with 2.0mm2 ground , single plase	432.00	mtrs	40.00	17,280.00			17,280.00
	3.5mm ² THHN Wire (Power Line)	432.00	mtrs			35.00	15,120.00	15,120.00
	2.0mm ² THHN Wire (Ground)	432.00	mtrs			18.00	7,776.00	7,776.00
	PVC Conduit & Accessories (30%)	150.00	mtrs			30.00	4,500.00	4,500.00
	Boxes, Connectors, Tape, Consumables	1.00	mtrs			2,000.00	2,000.00	2,000.00
13.0	T-5 LED Light, 18 watts, configured in continous line	153.00	pcs			450.00	68,850.00	68,850.00
14.0	Wiring works for production lighting thhn wire 2.0mm	8.00	box			3,850.00	30,800.00	30,800.00
15.0	Power outlets for office and Common areas 2 gang ruyo	6.00	set			450.00	2,700.00	2,700.00
16.0	Wiring THHN 3.5mm	4.00	box			7,800.00	31,200.00	31,200.00
17.0	Grill type Light fixture 2ft x 4ft 2x 18watts Led tube	20.00	set			3,570.00	71,400.00	71,400.00

18.0	Emergency Light s Rechargeable dual Led	4.00	pcs			1,450.00	5,800.00	5,800.00
19.0	Consumables	1.00	lot			7,500.00	7,500.00	7,500.00
SUB - TOTAL III								1,305,955.40
D	MECHANICAL WORKS							-
	ACU 1hp split type (LOBBY ROOM)	1.00	set	7,500.00	7,500.00	38,400.00	38,400.00	45,900.00
	ACU 1.5 hp split type(OFFICE ROOM)	1.00	set	9,500.00	9,500.00	40,800.00	40,800.00	50,300.00
	Production ACU 5 tr 6hp Ceiling suspended (DAIKIN)	4.00	set	25,000.00	100,000.00	195,300.00	781,200.00	881,200.00
	ECB 40AT NEMA 3R	6.00	set			1,800.00	10,800.00	10,800.00
	Wiring THHN 5.5mm	3.00	box			11,400.00	34,200.00	34,200.00
	Copper tube 5/8 X 20FT	6.00	roll			3,500.00	21,000.00	21,000.00
	Copper tube3/8X20FT	6.00	roll			2,800.00	16,800.00	16,800.00
	Insulation rubber 5/8	30.00	pcs			275.00	8,250.00	8,250.00
	PVC Tape	20.00	roll			250.00	5,000.00	5,000.00
	Bracket and support	1.00	lot			4,500.00	4,500.00	4,500.00
	PVC Pipe 3/4	20.00	pcs			240.00	4,800.00	4,800.00
	Consumables	1.00	lot			7,500.00	7,500.00	7,500.00
SUB - TOTAL IV								1,090,250.00
E	SUPPLY LABOR FOR INSTALLATION OF FIRE DETECTION AND ALARM SYSTEM	1.00	lot	75,000.00	75,000.00			75,000.00
	Manual Call Point Fire Alarm	4.00	set			1,080.00	4,320.00	4,320.00
	Fire Alarm Bell, 220V / 12V	4.00	set			780.00	3,120.00	3,120.00
	Main fire Alarm Control Panel(4 zone)	1.00	set			18,000.00	18,000.00	18,000.00
	Photoelectric Smoke Detector	20.00	pcs			147.00	2,940.00	2,940.00
	Strobe Light / Hom Strobe (Replacement of Defective Compounds)	1.00	lot			1,080.00	1,080.00	1,080.00
	Battery BA12V7SAH	2.00	pcs			2,760.00	5,520.00	5,520.00
	Flexible Metal hose, 3/4 inch	2.00	roll			1,020.00	2,040.00	2,040.00
	Flexible metal hose, 1/2 inch	2.00	roll			900.00	1,800.00	1,800.00
	EMT pipes, 3/4 inch	20.00	pcs			390.00	7,800.00	7,800.00
	EMT pipes,m 1/2 inch	25.00	pcs			288.00	7,200.00	7,200.00
	Metal Junction box, 4" by 4"	25.00	pcs			78.00	1,950.00	1,950.00
	TF Wire, twisted pair, 1.25mm2	3.00	roll			4,200.00	12,600.00	12,600.00
	GI Pull box, 40cm by 20 cm	1.00	set			4,120.00	4,120.00	4,120.00
	Assorted PVC fittings	1.00	lot			3,500.00	3,500.00	3,500.00
	Assorted EMT fittings	1.00	lot			4,500.00	4,500.00	4,500.00
	Hangers & brackets	1.00	lot			8,500.00	8,500.00	8,500.00
	Clamps, fitting & other consumables	1.00	lot			3,500.00	3,500.00	3,500.00
SUB - TOTAL VI								167,490.00
VI	Direct Cost							100,000
VII	OverHead,Contingencies and Miscellaneous							100,000
VIII	Contractor's Profit (CP)							100,000
VDX	Value Added Tax (VAT EX)							
X	Total Unit Cost							300,000
Terms And Condition				Note:				
Mode of Payment : 40% DP / 55% Weekly Progress Billing & 5% Retention (4mos)				*No PO, No DP, No Work				
Leadtime / Delivery: 40 working days				*Other items and / or scope of works that are not included in our proposal are subject to additional cost				
Warranty: 1 year workmanship				*Validity of proposal is 30days only				
We hope that the above foregoing will merit your approval and we will look forward for your order confirmation. Should you have any question on the above matter, please feel free to contact the undersigned. Thank you for giving us the opportunity to quote on your requirements								
ENGR. RENANTE M. VEGA OPERATION MANAGER RVR SQUARED MECHANICAL ENGINEERING SERVICES				ENGR. RITCHELL L. PANAGUITON GENERAL MANAGER RVR SQUARED MECHANICAL ENGINEERING SERVICES				